

Item	Description	Unit	Quantity	Rate	Amount
<p>PARTITION WORK FOR PARTITIONING OF ELDORET CBD CAMPUS AT SIRGOI BUILDING ALONG ODINGA OGINGA STREET BLOCK NO 7 PLOT NO 91 SECTION 2 PART A FOURTH FLOOR</p>					
<p><u>Gypsum Partition along corridor</u></p>					
A	12mm thick gypsum nailed on 75x50mm framework (ms) on both sides	SM	210		-
B	75X50mm wrot cypress timber nailed at 600mm centre to centre bothways	LM	550		-
C	75X50mm wrot cypress timber plugged to floor using 10mm dia raw bolts spaced at 1000mm centre to centre .				
<p><u>Skirting</u></p>					
D	95x20mm Wrot mahogany skirting with rounded top edge	LM	57		-
		LM	115		-
<p><u>PAINTING AND DECORATING</u></p>					
E	Sand hardwood skirting to a smooth surface, clean and apply two coats clear polyurethane varnish as Crown' or equal and approved to surfaces exceeding 100mm and not exceeding 200mm girth				
<p><u>Cornice</u></p>					
F	75x20mm cypress curved cornice rounded top edge	LM	115		-
		LM	145		-
G	Prepare and prime wood surfaces not exceeding 100mm girth before fixing	LM	145		-
H	Prepare and apply one undercoat and two coats gloss enamel paint on wood surfaces not exceeding 75mmgirth but not exceeding 150mm high	LM	145		-
G	Prepare and apply one undercoat and two coats of gloss oil paint on general wood surfaces	SM	200		-
I	4mm thick clear Georgian wired Glass sheet and glazing to metal with putty, with and including setting edges of glass in wash leather in panes sizes;	SM	32		-

	TOTAL				-
--	--------------	--	--	--	---

Item	Description	Unit	Quantity	Rate	Amount
	<p style="text-align: center;">PARTITION WORK FOR PARTITIONING OF ELDORET CBD CAMPUS AT SIRGOI BUILDING ALONG ODINGA OGINGA STREET BLOCK NO 7 PLOT NO 91 SECTION 2 PART B FOURTH FLOOR</p> <p style="text-align: center;"><u>Gypsum Partition Between partition 3000mm high</u></p>				
A	12mm thick gypsum nailed on 75x50mm framework (ms) on both sides	SM	121		-
B	75X50mm wrot cypress timber nailed at 600mm centre to centre bothways	LM	252		-
C	75X50mm wrot cypress timber plugged to floor using 10mm dia raw bolts spaced at 1000mm centre to centre .				
	<u>Skirting</u>	LM	21		-
D	95x20mm Wrot mahogany skirting with rounded top edge	LM	42		-
	<u>PAINTING AND DECORATING</u>				
E	Sand hardwood skirting to a smooth surface, clean and apply two coats clear polyurethane varnish as Crown' or equal and approved to surfaces exceeding 100mm and not exceeding 200mm girth				
	<u>Cornice</u>	LM	42		-
F	75x20mm cypress curved cornice rounded top edge	LM	42		-
G	Prepare and prime wood surfaces not exceeding 100mm girth before fixing	LM	42		-
H	Prepare and apply one undercoat and two coats gloss enamel paint on wood surfaces not exceeding 75mmgirth but not exceeding 150mm high	LM	145		-
G	Prepare and apply one undercoat and two coats of gloss oil paint on general wood surfaces	SM	121		-

I	4mm thick clear Georgian wired Glass sheet and glazing to metal with putty, with and including setting edges of glass in wash leather in panes sizes;	SM	80		-
TOTAL					-

Item	Description	Unit	Quantity	Rate	Amount
PARTITION WORK FOR PARTITIONING OF ELDORÉT CBD CAMPUS AT SIRGOI BUILDING ALONG ODINGA OGINGA STREET BLOCK NO 7 PLOT NO 91 SECTION 2 PART C FOURTH FLOOR					
<u>Gypsum Partition Between partition 2500mm high</u>					
A	12mm thick gypsum nailed on 75x50mm framework (ms) on both sides	SM	198		-
B	75X50mm wrot cypress timber nailed at 600mm centre to centre bothways	LM	99		-
C	75X50mm wrot cypress timber plugged to floor using 10mm dia raw bolts spaced at 1000mm centre to centre .				
<u>Skirting</u>					
D	95x20mm Wrot mahogany skirting with rounded top edge	LM	40		-
<u>PAINTING AND DECORATING</u>					
E	Sand hardwood skirting to a smooth surface, clean and apply two coats clear polyurethane varnish as Crown' or equal and approved to surfaces exceeding 100mm and not exceeding 200mm girth				
<u>Cornice</u>					
F	75x20mm cypress curved cornice rounded top edge	LM	80		-
G	Prepare and prime wood surfaces not exceeding 100mm girth before fixing	LM	80		-
H	Prepare and apply one undercoat and two coats gloss enamel paint on wood surfaces not exceeding 75mmgirth but not exceeding 150mm high	LM	80		-

G	Prepare and apply one undercoat and two coats of gloss oil paint on general wood surfaces	SM	198		-
I	4mm thick clear Georgian wired Glass sheet and glazing to metal with putty, with and including setting edges of glass in wash leather in panes sizes;	SM	0		-
TOTAL					-

Item	Description	Unit	Quantity	Rate	Amount
SECTION 2 PART D FOURTH FLOOR					
<u>Flush Door</u>					
A	D3 45mm Thick solid core flush door size 800x2050mm with mahogany veneer both sides and 45x20mm wrot hardwood lipping all round [D3]	No	15		-
<u>Frames and finishings</u>					
B	245x70mm Twice rebated and moulded frame plugged to stone walling	LM	105		-
C	45x20mm Moulded architrave planted on frame	LM	105		-
D	15x15mm Glazing bead to fanlight	LM	42		-
<u>Painting and Decorating</u>					
E	Prepare and prime wood surfaces not exceeding 100mm girth	LM	105		-
F	Prepare and prime wood surfaces exceeding 100mm and not exceeding 200mm girth	LM	105		-
G	Prepare and apply one undercoat and two coats clear polyurethane varnish on wood surfaces exceeding 200mm and not exceeding 300mm girth	LM	105		-
H	Prepare and apply one undercoat and two coats clear polyurethane clear varnish on general wood surfaces	SM	60		-
<u>Ironmongery</u>					
<u>Supply and fix the following ironmongery to hardwood with matching screws:-</u>					
I	100mm Brass butt hinges	Pair	23		-

J	2-Lever mortice lock as Union ref. 2295 with a pair of polished brass handles	No	15	-
K	38mm Diameter rubber door stop plugged to concrete or stone work	No	15	-
Total				-

BILL SUMMARY FOR SECTION

Item	Description				Amount
1	SECTION 2 PART A FOURTH FLOOR				-
2	SECTION 2 PART B FOURTH FLOOR				-
3	SECTION 2 PART C FOURTH FLOOR				-
4	SECTION 2 PART D FOURTH FLOOR				-
TOTAL					-

Item	Description	Unit	Quantity	Rate	Amount
	<u>SECTION 5 PROVISIONAL COST</u>				
	<u>PRIME COST (P.C) AND PROVISIONAL SUMS</u>				
	<u>Works which are covered by the Prime Cost (P.C) sums are to be executed by Nominated Sub-contractors under the direction of the Estate Manager</u>				
	<u>ELECTRICAL WORKS</u>				
	<u>K.P. & L.C SERVICE LINE</u>				

D	Allow the P.C sum of Kenya shillings Two Hundred thousand only (Ksh200,000/=) for Electrical Works	sum			
E	Allow for main contractor's profit				
F	Allow for attendance	sum			
Total					

BILL SUMMARY FOR SECTION

Item	Description				Amount
1	SECTION 2 FOURTH FLOOR GYPSUM PARTITION				-
2	SECTION 5 PROVISIONAL COST				-
3	<i>Provide a contigence upon direction by the DVC F</i>				
		SUM	1	250000	250,000.00
Total					